








## EELE408 Photovoltaics

### Lecture 22: Grid Tied Systems

**Dr. Todd J. Kaiser**  
 tjkaiser@ece.montana.edu  
 Department of Electrical and Computer Engineering  
 Montana State University - Bozeman

MultiCrystalline on Metal Roof



7




8

Shed roof sloped the wrong direction

- Shed roof sloped the wrong direction
- Aluminum frame work to tilt the array

9

Rear View of Array System



Aluminum Frame work  
Can see the solar cell pattern through the modules

10


Bozeman City Hall



Two inverters in this systems

11

Photovoltaic & Solar Heating



Hot water tilted for winter optimization

12

**MONTANA** State University | College of Engineering




Newer panels are entirely black  
Rear Contacts



13

**MONTANA** State University | College of Engineering

System Grid Interface




Shut off

Net Metering

Inverter

Monitoring

Electrical Panel



14

**MONTANA** State University | College of Engineering

Exterior Labeled PV Disconnect Required



PHOTOVOLTAIC  
SYSTEM  
DISCONNECT



15

**MONTANA** State University | College of Engineering


Inverter




16

**MONTANA** State University | College of Engineering

Inverter Readout



SUNPOWER


E-total 2328kWh  
h-total 1997h

Operation

Earth Fault

Failure


Has been in operation for 181 days  
Producing 840 kWh per month on average



17


**MONTANA** State University | College of Engineering

Net Metering



NET METER

38 452 004



18

Additional Disconnects

19

Wireless Monitoring System

- Newer systems have an add-on where the system parameters can be sent to computer network.

20

Grid Tied with Battery backup

21

Small System with Battery Backup

22

48 Volt Battery Backup

23

Inverter and Charge Controller

24

**Inverter**



25

**Read-out**



26

**New solar tracking system on 'M' trail**



27

**Kaiser Shop/Garage #1**

<ul style="list-style-type: none"> <li>• <b>System Specifications</b></li> <li>- Rated Power = 5,040 W</li> <li>- 24 panels: Kyrocera 210</li> <li>- Inverter: Fronius IG 5.0             <ul style="list-style-type: none"> <li>• 5000 W</li> <li>• 240V – 21 A</li> </ul> </li> <li>- Unirac SunFrame</li> <li>- Estimated Production</li> <li>- <b>529 kW –hr / month</b></li> <li>- <b>\$7.14/W</b></li> </ul>	<ul style="list-style-type: none"> <li>• <b>Price Estimate</b></li> <li>- Solar Modules (24) \$20k</li> <li>- Inverter \$ 5k</li> <li>- Racking \$ 3k</li> <li>- Wiring \$ 1k</li> <li>- Installation \$ 7k</li> <li>- <b>Total \$36k</b></li> <li>- NW Energy Grant -\$6k</li> <li>- 30% Federal Tax Credit \$9k</li> <li>- State Tax Credit \$0.5</li> <li>- <b>Cost after Incentive \$20.5k</b></li> </ul>
--	---

28

**Kaiser Shop/Garage #2**

<ul style="list-style-type: none"> <li>• <b>System Specifications</b></li> <li>- Rated Power = 6,750 W</li> <li>- 30 panels: SunPower 225</li> <li>- Inverter: SPR 7000m             <ul style="list-style-type: none"> <li>• 7000 W</li> <li>• 240V – 29 A</li> </ul> </li> <li>- Unirac SunFrame</li> <li>- Estimated Production</li> <li>- <b>709 kW –hr / month</b></li> <li>- <b>\$6.81/W</b></li> </ul>	<ul style="list-style-type: none"> <li>• <b>Price Estimate</b></li> <li>- Solar Modules (30) \$30k</li> <li>- Inverter \$ 5k</li> <li>- Racking \$ 3k</li> <li>- Wiring \$ 1k</li> <li>- Installation \$ 7k</li> <li>- <b>Total \$46k</b></li> <li>- NW Energy Grant -\$6k</li> <li>- 30% Federal Tax Credit \$12k</li> <li>- State Tax Credit \$0.5</li> <li>- <b>Cost after Incentive \$27.5k</b></li> </ul>
---	--


29

**Kaiser Shop/Garage #3**


<ul style="list-style-type: none"> <li>• <b>System Specifications</b></li> <li>- Rated Power = 10,080 W</li> <li>- 48 panels: Kyrocera 210</li> <li>- Inverter: Fronius IG 10.0             <ul style="list-style-type: none"> <li>• 5000 W</li> <li>• 240V – 41.7 A</li> </ul> </li> <li>- Unirac SunFrame</li> <li>- Estimated Production</li> <li>- <b>1058 kW –hr / month</b></li> <li>- <b>\$6.35/W</b></li> </ul>	<ul style="list-style-type: none"> <li>• <b>Price Estimate</b></li> <li>- Solar Modules (48) \$40k</li> <li>- Inverter \$ 8k</li> <li>- Racking \$ 5k</li> <li>- Wiring \$ 1k</li> <li>- Installation \$ 10k</li> <li>- <b>Total \$64k</b></li> <li>- NW Energy Grant -\$6k</li> <li>- 30% Federal Tax Credit \$17k</li> <li>- State Tax Credit \$0.5</li> <li>- <b>Cost after Incentive \$40.5k</b></li> </ul>
---	---

30

Kaiser Shop/Garage #4



<ul style="list-style-type: none"> <li>• <b>System Specifications</b> <ul style="list-style-type: none"> <li>- Rated Power = 13,500 W</li> <li>- 60 panels: SunPower 225</li> <li>- Inverter: SPR 7000m (2)                             <ul style="list-style-type: none"> <li>• 7000 W</li> <li>• 240V – 29 A</li> </ul> </li> <li>- Unirac SunFrame</li> <li>- Estimated Production</li> <li>- <b>1417 kW –hr / month</b></li> <li>- <b>\$6.37/W</b></li> </ul> </li> </ul>	<ul style="list-style-type: none"> <li>• <b>Price Estimate</b> <ul style="list-style-type: none"> <li>- Solar Modules (60) \$60k</li> <li>- Inverter \$ 9k</li> <li>- Racking \$ 5k</li> <li>- Wiring \$ 2k</li> <li>- Installation \$ 10k</li> <li>- <b>Total \$86k</b></li> <li>- NW Energy Grant -\$6k</li> <li>- 30% Federal Tax Credit \$24k</li> <li>- State Tax Credit \$0.5</li> <li>- <b>Cost after Incentive \$55.5k</b></li> </ul> </li> </ul>
---	---


31

**Stand Offs**

Stand offs are screwed into the roof rafters after the roof has been dried in with a membrane





Near the panel closest to the electrical panel a feed through is positioned.

**Electrical Feed Through**



Flashing is placed around each of the standoffs as the roofing shingles are positioned and nailed.

**Standoff Flashing**



Once the roof has been shingled (opposite side) the panels are delivered with the balance of the system.

**Panel Installation (2 days)**



**Rail System**

Vertical rails are secured on the standoffs.

